

P R E V E N T I V
OBJEKTI : REHABILITIMI I RRUGEVE, SHESHEVE E FASADAVE
BLLOKU TEK LAGJA NR.2

POGRADEC 2020

Nr	Nr.Analiz	PERSHKRIMI I PUNIMEVE	Njesi	Sasia	Cmimi	Vlera
a	b	c	1	2	3	4
A. RRUGA "RINIA"						
I. PUNIME NE RRUGE						
1	2.426/3+	Prishje shtresa betoni,bordura ekzist+trans. 10 km	m3	55		
2	An +	Heqje pllaka t=8 cm e transp auto 2km	m3	220		
3	3.89/b+2.	Germim esk.gome e trans. dheu,10km.	m3	600		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	2600		
5	3-212/a	Shtrese stabilizanti t=5 cm	m2	2340		
6	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	2340		
7	3.226/2	Shtrese asfaltobetoni me granil guri kave, 5cm, me makineri	m2	2340		
8	3.619	F.V bordura betoni 25x35 cm	ml	550		
9	3.244	Beton C 20/25 per kuneten	m3	100		
		SHUMA I	LEK			
II. PUNIME NE TROTUARE						
1	An +	Heqje pllaka t=6cm e transp auto 2km	m3	114		
2	3.89/b+2.	Germim esk.gome e trans. dheu,10km.	m3	456		
3	3.209	Shtrese çakelli mbeturine kave t=10 cm, perhapur e ngjeshur makineri	m2	1900		
4	3-212/a	Shtrese stabilizanti t=5 cm	m2	1900		
5	2.262/3	Shtrese betoni C 12/15	m3	190		
	2.264	Shtrese lluster çimento 1:2	m2	1900		
6	2.266/1	Shtrese me pllaka granili me boje 30x30 cm	m2	1900		
7	3-619/a	FV bordura betoni C16/20 P.F (6x20)cm kont.peme	ml	200		
8	3-243	Beton C16/20 per konturim trotuari, mur, shkalle	m3	42		
9	Analize	F.V kosha	cope	30		
		SHUMA II	LEK			
III. KANALIZIME TE UJRAVE ATMOSFERIKE						
1	3.89/a+2.	Germim me esk me goma dheu kanale e puseta +trans. 10km	m3	390		
2	2-261	Shtrese e mbushje me rere(granil) rreth tubit plastik	m3	150		
3	3-An/1t	FV tub plastik HDPE Ø 315 mm I brinjezuar	ml	550		
4	3An-	Mbushje cakull gurore. mbi tub plastik ngjesh mak.	m3	240		
5	2-An-23	Pusete gratar b/a C16/20 (40x60x100)cm me zgare gize te fiksuar	komp	20		
6	2-575	Pusete kontrolli beton C16/20 (1x1x1.5)m me kapak gize rrethor Ø 60cm	komp	4		
7	Analize	Rakordim puseta ekzistuese te vogla	cope	30		
8	Analize	Rakordim puseta ekzistuese te medha	cope	15		
		SHUMA III	LEK			
IV. PUNIME NDRICIMI RRUGOR + SINJALISTIKE						
1	3.An+pr	F.V Ndriques Dekorativ LED 100w , trupi per alumini te anodizuar	Cope	15		
2	3.An.122	Vjiëzim shirita gjatesor me gjeresi 12cm	ml	520		
3	3.An.127	Vjiëzim shirita gjatesor me gjeresi 15cm	ml	260		
4	3.An.137	Vjiëzim shirita terthor me gjeresi 30 cm	ml	315		
5	3.An.106	Tabele trekendore normal	cope	4		
6	3.An.50	Tabele drejtkendore (treguese)	cope	10		
7	3.An.100	Tabele rrethore " detyrimi " normal	cope	4		

8	3.An.103	Tabele rrethore " ndalimi " normal	cope	10		
9	3.An.97	Tabele tetekendore normal	cope	6		
		SHUMA IV				
A	RRUGA "RINIA" TOTAL		LEK			
B.RRUGA "RESHIT COLLAKU"						
		I. PUNIME NE RRUGE				
1	2.426/3+	Prishje shtresa betoni,bordura ekzist+trans. 10 km	m3	42		
2	An +	Heqje pllaka t=8 cm e transp auto 2km	m3	230		
3	3.89/b+2.	Germim esk.gome e trans. dheu,10km.	m3	650		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	2800		
5	3-212/a	Shtrese stabilizanti t=5 cm	m2	2400		
6	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	2400		
7	3.226/2	Shtrese asfaltobetoni me granil guri kave, 5cm, me makineri	m2	2400		
8	3.619	F.V bordura betoni 25x35 cm	m	760		
9	3.244	Beton C20/25 per kuneten	m3	160		
		SHUMA I				
		II. PUNIME NE TROTUARE				
1	An +	Heqje pllaka t=6cm e transp auto 2km	m3	90		
2	3.89/b+2.	Germim esk.gome e trans. dheu,10km, per kason.	m3	360		
3	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	1300		
4	3-212/a	Shtrese stabilizanti t=5 cm	m2	1300		
5	2.262/3	Shtrese betoni C 12/15 10 cm	m3	130		
	2.264	Shtrese lluster çimento 1:2	m2	1300		
6	2.266/1	Shtrese me pllaka granili me boje 30x30 cm	m2	1300		
8	3-619/a	FV bordura betoni C16/20 P.F (6x20)cm kont.peme	ml	200		
9	3-243	Beton C16/20 per konturim trotuari, mur, shkalle	m3	53		
10	Analize	F.V kosha	cope	30		
		SHUMA II	LEK			
		III. KANALIZIME TE UJRAVE ATMOSFERIKE				
1	3.89/a+2.	Germim me esk me goma dheu kanale e puseta +trans. 10km	m3	600		
2	2-261	Shtrese e mbushje me rere(granil) rreth tubit plastik	m3	180		
3	3-An/1t	FV tub plastik HDPE Ø 315 mm I brinjezuar	ml	800		
4	3An-	Mbushje cakull gurore. mbi tub plastik ngjesh mak.	m3	360		
5	2-An-23	Pusete gratar b/a C16/20 (40x60x100)cm me zgare gize te fiksuar	komp	30		
6	2-575	Pusete kontrolli beton C16/20 (1x1x1.5)m me kapak gize rrethor Ø 60cm	komp	6		
7	Analize	Rakordim puseta ekzistuese te vogla	cope	30		
8	Analize	Rakordim puseta ekzistuese te medha	cope	15		
		SHUMA III	LEK			
		IV. PUNIME NDRICIMI RRUGOR + SINJALISTIKE				
1	3.An+pr	F.V Ndriçues Dekorativ LED 100w , trupi per alumini te anodizuar	Cope	20		
2	3.An.122	Vjiëzim shirita gjatesor me gjeresi 12cm	ml	800		
3	3.An.127	Vjiëzim shirita gjatesor me gjeresi 15cm	ml	400		
4	3.An.137	Vjiëzim shirita terthor me gjeresi 30 cm	ml	450		
5	3.An.106	Tabele trekendore normal	cope	6		
6	3.An.50	Tabele drejtkendore (treguese)	cope	14		
7	3.An.100	Tabele rrethore " detyrimi " normal	cope	6		
8	3.An.103	Tabele rrethore " ndalimi " normal	cope	16		
9	3.An.97	Tabele tetekendore normal	cope	9		
		SHUMA IV	LEK			
B	RRUGA "RESHIT COLLAKU" TOTAL		LEK			

C . RRUGA "GANI BUTKA"						
		I. PUNIME NE TROTUARE				
1	An +	Heqje pllaka t=6cm e transp auto 2km	m3	36		
2	2.426/3+	Prishje shtresa betoni,bordura ekzist+trans. 10 km	m3	25		
3	3.89/b+2.	Germim esk.gome e trans. dheu,10km, per kason.	m3	130		
4	3.209	Shtrese çakelli mbeturine kave t=10cm, perhapur e ngjeshur makineri	m2	850		
5	3-212/a	Shtrese stabilizanti t=5 cm	m2	850		
6	2.262/3	Shtrese betoni C 12/15	m3	85		
7	2.264	Shtrese lluster çimento 1:2	m2	850		
8	2.266/1	Shtrese me pllaka granili me boje 30x30 cm	m2	850		
9	3.619	F.V bordura betoni 25x35 cm	ml	250		
10	3-619/a	FV bordura betoni C16/20 P.F (6x20)cm kont.peme	ml	90		
11	3-243	Beton C16/20 per konturim trotuari, mur, shkalle	m3	130		
12	Analize	F.V kosha	cope	15		
13	3.An.164	Mbjellje peme dekorative	cope	10		
14	3.643	Mbjellje me bar	m2	120		
		SHUMA II	LEK			
C	RRUGA "GANI BUTKA" TOTAL			LEK		
D. BLOKU RINIA						
		I. PUNIME NE TROTUARE				
1	2.426/3+	Prishje shtresa betoni,bordura ekzist+trans. 10 km	m3	120		
2	2.426/2+	Prishje mure me blloqe betoni,trans. 3 km	m3	42		
3	2.426/1	Prishje mure tulle me pastrim	m3	21		
4	2.88	Mur me blloqe betoni t=20cm ll.perzier M-15	m3	12		
5	An +	Heqje pllaka t=6cm e transp auto 2km	m3	554		
6	3.89/b+2.	Germim esk.gome e trans. dheu,10km, per kason.	m3	588		
7	3,210	parkime	m2	1690		
8	3-212/a	Shtrese stabilizanti t=5 cm	m2	1690		
9	2.286+pe	FV pllaka betoni C25/30 t=6 cm mbi shtrese rere, t=5cm	m2	1478		
10	2.286+pe	FV pllaka betoni C25/30 t=8 cm mbi shtrese rere, t=5cm, parkim i ri	m2	348		
11	3-617/1	FV bordura betoni C16/20 P.F (15x30)cm mbi beton	ml	1948		
12	3-618	FV bordura betoni C16/20 P.F (20x35)cm mbi beton	ml	712		
13	3-619/a	FV bordura betoni C16/20 P.F (6x20)cm kont.peme	ml	170		
14	3-243	Beton C16/20 per konturim trotuari, mur, shkalle	m3	30		
15	2.64/1	Mur me tulla te plota, lartesi deri 3m, ll.perzier M-15	m3	6		
16	Analize	F.v stola dekorative	cope	36		
17	Analize	F.V kosha	cope	46		
18	3.An.164	Mbjellje peme dekorative	cope	70		
19	3.643	Mbjellje me bar	m2	1290		
		SHUMA I	LEK			
		II. KANALIZIME TE UJRAVE ATMOSFERIKE				
1	2.426/3+	Prishje shtresa betoni, asfalti +trans.deris 10 km	m3	68		
2	3.89/a+2.	Germim me esk me goma dheu kanale e puseta +trans. 10km	m3	370		
3	2-261	Shtrese e mbushje me rere(granil) rreth tubit plastik	m3	187		
4	2.523	FV tub plastik HDPE Ø 200 mm I brinjezuar	ml	503		
5	3-An/1t	FV tub plastik HDPE Ø 315 mm I brinjezuar	ml	244		
6	3.An/2t	FV tub plastik HDPE Ø 400 mm I brinjezuar	ml	230		
7	3.An-57	F.v tub çeliku Ø = 315mm	ml	7		
8	3.An-57	F.v tub çeliku Ø = 219mm	ml	15		
9	3An-	Mbushje cakull gurore. mbi tub plastik ngjesh mak.	m3	140		
10	2-An-23	Pusete gratar b/a C16/20 (40x60x100)cm me zgare gize te fiksuar	komp	36		

11	2-575	Pusete kontrolli beton C16/20 (1x1x1.5)m me kapak gize rrethor Ø 60cm	komp	4		
12	3-244	Beton C20/25 per kuneten	m3	70		
		SHUMA II	LEK			
		III. PUNIME NDRICIMI RRUGOR				
1	3.45/1+3.	Germim + mbushje rere e çakull kanal linje furnizimi	m3	110		
2	2.480/5	F.V tub plastmasi Ø 31 ~ 36 mm	ml	340		
3	4-	F.v kabell elektrik Cu (5x4)mm2	ml	410		
4	2.a-73	F.v kunja tokezimi xingato 4flete H = 1.5M	cope	27		
5	3- 242	Bllok betoni C 12/15 fiksime kantelabri	m3	4		
6	3.An/53p	F.v kantelaber ndriçimi H = 5m	cope	20		
7	3.An/53	F.v kantelaber ndriçimi H = 7m	cope	7		
8	3.An/pr	F.V Ndrriçues Dekorativ LED 100w , trupi per alumini te anodizuar	cope	43		
	3.An/pr	F.V Ndrriçues Dekorativ LED 50w , trupi per alumini te anodizuar	cope	65		
9	4-155/3	F.v limitator 10A	cope	27		
10	3. An 56	F.v tub çeliku Ø 80mm per kalim rruge	ml	8		
11	4.142/1.1	F.V.kabllo kontrolli Cu pa armuar, ne mure e konstruksione, 4x1.5 mm2	ml	220		
		SHUMA III	LEK			
		IV. PUNIME NE RRUGE E SHESHE				
1	3.197/1+	Prishje shtresa asfalti,cakulli makineri + trans.derri 10 km	m2	420		
2	3.89/b+2.	Germim dheu me eskavator rrota goma +trans derri 10 km	m3	420		
3	3.212	Shtrese cakull t= 10/15 cm,makadam, perhapur e ngjeshur me makineri	m2	1420		
4	3-212/a	Shtrese stabilizanti t=5 cm	m2	1420		
5	Analize	Rakordim puseta ekzistuese te vogla	cope	32		
6	Analize	Rakordim puseta ekzistuese te medha	cope	14		
7	3.243/1	Mur betoni C.16/20	m3	10		
8	3.An	Skarifikim shtrese asfalti me makineri 4cm	m2	7120		
9	3.An	Spërkatje me emulsion bituminoz 0.5 l/m2	m2	9680		
10	3.222/1	Shtrese binderi me granil guri kave 5 cm me makineri	m2	1420		
11	3.226/1	Shtrese asfaltobetoni me granil guri kave 4 cm me makineri	m2	11100		
12	3.An.122	Vjiëzim shirita gjatesor me gjerësi 12cm	ml	1286		
13	3.An.127	Vjiëzim shirita gjatesor me gjerësi 15cm	ml	3250		
14	3.An.137	Vjiëzim shirita terthor me gjerësi 30 cm	ml	255		
15	3.An.106	Tabele trekendore normal	cope	6		
16	3.An.50	Tabele drejtkendore (treguese)	cope	14		
17	3.An.100	Tabele rrethore " detyrimi " normal	cope	6		
18	3.An.103	Tabele rrethore " ndalimi " normal	cope	14		
19	3.An.97	Tabele tetekendore normal	cope	8		
		SHUMA IV	LEK			
D	BLLOKU RINIA TOTAL			LEK		
E. RIKONSTRUKSION FASADASH						
		I. PUNIME NE FASADAT				
1	2.426	Prishje mur tulle pa pastrim	m³	6		
2	Analize	Prishje suvaje	m²	11527		
3	2.220	valezuar	m²	1200		
4	An	Veshje fasade me alukoband	m²	425		
5	2.352	Suva fasade me granil e çimento te zak, h > 8m.	m²	52750		
6	2.350	Suva xokoli me granil e çimento te zakonshme me spruco	m²	4161		
7	2.404/1	Boje hidroplastike importi cilesi e I-re	m²	52750		
8	Analize	Cmontim dritare te kafazi I shkalleve	m²	828		
9	2..375	F v dritare d/alumini te kafazi I shkalleve	m²	828		
10	2.203	Veshje kornize llamarine xingat	m²	1580		

11	2.209/a	Ulluk shkarkimi vertikal me PVC Ø 120mm	ml	450		
12	2.206	Kasete shkarkimi me llmarine xingat	cope	57		
		SHUMA I	LEK			
E	RIKONSTRUKSION FASADASH TOTAL					LEK
		A + B + C + D + E				
		FONDI REZERVE 4.9 %	LEK			
		SHUMA	LEK			
		T.V.SH 20 %	LEK			
		SHUMA	LEK			

HARTUAN PREVENTIVIN

Ing. Violeta ÇEKANI

Ark.Dhimitraq GJATA

Ing. Ermira XHAJA

Ark.Veselina GUSHO

Urb. Erladi PETANI