

**MIRATOHET
BASHKIA MIRDITË
KRYETARI**

Z. NDREC DEDAJ

PREVENTIV PA ÇMIME

Objekti : Rikonstruksion i Rruges "Rreshen- Fshati Sheshaj "

Nr	Analiza	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
I.		Punime ne rruge				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	13405		
2	3.124/1a	Germim shkambi mesatar me çekiç me ekskavator me zinxhir	m ³	5600		
3	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	12582		
4	3.198	Cilindrim kasonete me Rrul	m ²	28529		
5	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	6423		
		SHUMA I				
II.		Punime Shtresash				
1	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri (shtresa I)	m ²	28529		
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri (shtresa II)	m ²	28529		
3	3.212/c	Shtrese stabilizanti t=15cm	m ²	28529		
4	3.212/b	Shtrese stabilizanti t= 10 cm per bankine	m ²	7781		
5	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m ²	20748		
6	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m ²	20748		
7	3.244/1	Struktura te holla monolite betoni C 20/25 (kuneta)	m ³	311		
8	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	45		
9	3.618	F V bordura betoni 20x35 cm	ml	55		
		SHUMA II				
III.		Punime per ndertim vepra arti				
1	3.46/1	Germim kanalesh ne toke te forte, me krahe, me seksion deri 0.75 m ²	m ³	2199		
2	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	163		
3	3.633	Fugature llac cemento M - 50, Mur guri	m ²	134		
4	An-8	Mbushje me cakell pas mureve	m ³	1449		
5	3.244/1	Struktura te holla monolite betoni C 20/25 (Mure)	m ³	1262		
6	2.520	Tub per drenazh pvc Ø 110 mm	ml	505		

7	3.244/1	Struktura te holla monolite betoni C 20/25 (Kanale)	m ³	683		
8	2.262/4	Shtrese betoni C 16/20 (veshje kanali)	m ²	35		
9	3.193/a	Shtrese zhavor lumi t=10cm, me cilindrim	m ²	2324		
10	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	0.52		
11	3.323	Mur guri mbajtes e themele, llaç çimento M50 (prita malore)	m ³	72.4		
12	An-49	Prishje struktura prej betoni (tombino dhe kanale ekzistuese)	m ³	183		
		SHUMA III				
IV.		Punime per Vepra Arti				
1	3.46/1	Germim kanalesh ne toke te forte, me krahe, me seksion deri 0.75 m ²	m ³	377		
2	An-31	Gjeotekstil me gramature 180 g/m2	m ²	6195		
3	3.193/a	Shtrese zhavor lumi t=10cm, me cilindrim	m ²	5445		
4	3.179	Ndertim kasonete ne toke mesatare	m ²	5445		
5	3.244/1	Struktura te holla monolite betoni C 20/25 (portale dhe mbingritje muresh,etj.)	m ³	122		
6	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	6		
7	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	6		
8	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	m	14		
9	An	Tub Celiku per kalim rruge fi 300	ml	60		
10	3.376	Ndertim drenazhi, mbushje me gure kave	m ³	240		
		SHUMA IV				
V.		Sinjalistika				
1	An125	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Termoplastike (sprajt)	ml	10374		
2	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	416		
3	An158	FV tabela te ndryshme rrugore D=60cm	cope	4		
4	An97	Tabela tetekendore normal me A-B, 90-30 (STOP)	cope	1		
5	An105	Tabela trekendore e vogel me A = 60	cope	67		
6	An48	Tabele katrore normal me A=60	cope	2		
7	An60	Sinjale "emër rruge" LxH normal 100x25	cope	3		
8	An119	Pervijues modulare te kthesave (cifte)	cope	18		
		SHUMA V				
		PERMBLEDHESE				
		SHUMA I+II+III+IV+V				
		Fondi rezerve	3%			
		SHUMA				
		TVSH	20%			
		SHUMA TOTALE				

Shenim: Cmimet e preventivit jane ne baze manualit te cmimeve te ndertimit viti 2015.

Preventivues :
"ERALD-G" shpk

Ing. Gezim ISLAMI