

PREVENTIV**EMERTESA OBJEKTIT: "NDERTIMI I BYPASS-IT NE QENDREN HISTORIKE (URA E NANXES-URAT E MEDHA DUNAVAT)"**

BASHKIA GJIROKASTER

GJATESIA TOTALE = 980ML

Gjeresia Asfaltike 6 ML

Nr	Nr.analize	EMERTIMI I PUNIMIT	Nesi	Sasia	Cmimi	Vlera
I-PUNIME GERMIMI						
1	3.104/a	Germim dheu me ekskavator zingjir 0.5 m³, ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m3	33357		0
2	3.353	Mbushje me shkemb te germuar me pare	m3	3965		0
3	3.124/1a	Germim shkemb mesatar me çekiq me ekskavator me zinxhir	m3	3965		0
4	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	37322		0
5	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	31873		0
PUNIME PER SISTEMIMIN E SKARPATEVE						
1	3.161/1	Rrafshim skarpate ne germim, ekskavator 0.5 m3	m2	3722		0
2	An-30	Mbrojtja e shpateve nga renia e gureve me rrjete teli heksagonal 6x8 dhe diameter 2.2-2.4 mm te veshur me galfan(Zn-5%Al) me bordature anesore Ø 3.4/3.0 mm	m2	3722		0
3	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1.76		0
4	AN	Veshje shpati me shtrese vegjetale "Green fix,	m²	3722		0
5	An+3.An.55	F.V. Tub drenazhi Ø65mm	ml	494		0
6	3.454	Shpim me sonde Ø 0.8 m, ~ 15 m, (perde mbajtese).	m	564		0
7	3.245	Struktura monolite betoni me cakell C 25/30(Pilota, Trau)	m3	593		0
8	3.244	Struktura monolite betoni C 20/25,(muri mbajtes)	m3	270		0
9	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	79		0
10	An-164	F.V. Fidane Peme dekorative	cop	326		0
11	2.262/4	Shtrese betoni C 16/20 (per kanalet e kullimit ne te dy krahete e rruges)	m3	630		0
12	3.183/a	Shtrese zhavor lumi t=10cm	m2	1003		0
13	An - 22	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	32		0
SHUMA I						0
II-PUNIME BETONI						
BOX B/A						
1	3.245	Struktura monolite betoni me cakell C 25/30	m3	9080		0
2	2.262/4	Shtrese betoni C 16/20 (per nivelim bazamenti)	m3	2937		0
3	3.183/b	Shtrese zhavor lumi t=15cm (niveluse e bazamentit)	m2	5292		0
4	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	65		0
5	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1237		0
6	An 19	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	5		0
7	3.624	H/izolim me emulsion ,2 duar bitum	m2	14535		0
8	3.121/a	Germim shkemb i coptuar me ekskavator 0.5 m³, shkemb, prani uji ~2m, themele gjeresi ~2 m, me shkarkim ne toke,	m3	2163		0
9	3.158/4a	Transport dheu me auto deri 4.0 km	m3	2163		0
10	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri(kanali me gjatesi 495.1m)	m2	4951		0
11	2.262/4	Shtrese betoni C 16/20 (per kanalin me gjatesi 495.1m)	m3	2313.4		0
12	2.182	Konstruksione metalike te thjeshta (zgare metalike)	ton	0.64		0
SHUMA II						0
III-PUNIME SHTRESASH						
1	3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	8580		0
2	3.193/b	Shtrese zhavor lumi t=20cm, me cilindrim	m2	8580		0
3	3.212/c	Shtrese stabilizanti, t=15 cm, perhapur dhe ngjeshur me makineri	m²	7897		0
4	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m²	6936		0
5	3.226/1	Shtrese asfaltobetoni me granil guri kave, t=4 cm, me makineri	m²	6936		0
6	2.262/4	Shtrese betoni C 16/20	m3	104		0
SHUMA III						0
IV-PUNIME NE TROTUAR						
1	3.193/b	Shtrese zhavor lumi t=20cm, me cilindrim	m2	5249		0
2	2.262/4	Shtrese betoni 10 cm per trotuare C16/20	m3	314.94		0
3	An	F+V Pllake guri (gelqeror) l bardhe i shuarar,kuadratur dhe tarakuar t=6cm per trotuar	m2	2,726		0
4	An	F+V Pllake guri l zi i shuarar,kuadratur dhe tarakuar t=6cm per trotuar	m2	2,726		0
5	3.617/1	F V bordura betoni 15x30 cm	ml	2095		0
6	2.262/4	Shtrese betoni C 16/20 (bordura kufizuese per bordurat)	m3	167.6		0
7	3.238	Struktura monolite betoni C 6/10	m3	187		0
SHUMA IV						0
V-PUNIME PER NDRICIMIN RRUGOR						
1	3.An/53	F V shtylla metalike per ndricim, H=7m	cope	60		0
2	3.An	FV ndricues Led 74W, 4000K, rendiment 138lm/W, IP66	cope	60		0

4	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	60		0
5	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	60		0
6	2.262/3	Shtrese betoni C 12/15	m3	10		0
7	4.131/3.5	F.V. Kabell 0,6/1 KV ; tip RG7R ; 4x10mm2	ml	1000		0
8	An	F.V. Kabell 0,6/1 KV ; tip RG7R ; 3x1,5mm2	ml	2050		0
9	Δn	F.v Tub fleksibel me dy shtresa d=90mm	ml	690		0
10	An	F V kuader komandimi komplet me santeri+fotoelement	cope	1		0
11	An+2,523	Tub pvc Ø 200 (inkastrimin e shtylles)	ml	80		0
12	An	F.V. Kabell FG7O R06/1KV 4X6mm	ml	1000		0
SHUMA V						0
VI-PUNIME K.U.B						
1	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	2305.2		0
2	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	62		0
SHUMA VI						0
VII-PUNIME K.U.Z						
1	3.103/a	Germim dheu me ekskavator zingjir 0.5 m³, ne kanale gjeresi deri 2 m, prani uji ~2m, kategoria IV, me shk ne toke	m3	623		0
2	2.258	Mbushje me zhavori	m3	223		0
3	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	2645		0
4	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	73		0
SHUMA VII						0
VIII- FIBRA OPTIKE DHE SHERBIMET INXHINIERIKE NENTOKESORE						
1	2.52	Tub pvc Ø 110 mm per linjen rezerve	ml	2,940.00		-
2	3.182/a	Shtrese rere natyrore t=10cm	m2	880.00		-
3	2.An - 19	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	25.00		-
Shuma VIII						0
IX -PUNIME TE NDRYESHME+SINJALISTIKA						
1	An105	F.V Tabela trekendore e vogel me A = 60	cope	3		0
2	An103	Tabele rrethi "ndalim" normal me D = 60	cope	8		0
3	An48	Tabele katrore normal me A=60	cope	8		0
4	An151	Vizime me boje bikomponente(kembesore +stop)	m2	55		0
5	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	2572		0
SHUMA IX						0
X -PUNIME GJELBERIMI						
1	3.104/a	Germim dheu me ekskavator zingjir 0.5 m³, ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m3	50		0
2	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	1100		0
3	An-164	F.V. Fidane Peme dekorative	cop	12		0
4	3643	Mbjellje bari ne skarpate	m²	900		0
5	An165	F.V. Fidane shkurre dekorative "Oleander"	cope	100		0
6	2.262/4	Shtrese betoni 10 cm per trotuare C16/20	m3	71		0
7	2.262/4	Shtrese betoni 20 cm per trotuare C16/20(per shkallet e gurit)	m3	21		0
8	An	Ndertim shkalle guri	m2	106		0
9	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	4.4		0
SHUMA X						0
		SHUMA I-VIII				0
		Fond rezerve 5%				0
		SHUMA PA TVSH				0
		T.V.SH. 20%				0
		TOTALI				0
1	An	F.V Stola betoni me ndenjese me binare druri 5x5 cm komplet 3x1 m	cop	32		0
		TOTALI				0

PREVENTIVOI

Studio "ZENIT & CO" SH.P.K

ADMINISTRATORI

Ing. ARQILE PERI