

PREVENTIV PUNIMESH

OBJEKTI: RIKONSTRUKSIONI I RRUGES PLIREZ - MALI TOMORR 23 KM
POROSITËSI: BASHKIA POLICAN

NR.	AN.	ZERAT E PUNIMEVE	NJËSIA	SASIA	ÇMIMI	VLERA
		I - Punime dheu LOTI II				
1	3.2	Prerje bime te vogla Ø10cm	m ²	28,000.00		
2	3.5	Preje e sistemim pemesh Ø 41- 75 cm	cope	700.00		
3	3.121/b	Germim shkemb i coptuar me ekskavator 0.5 m ³ , shkemb, prani uji ~2m, themele gjeresi >2 m, me shkarkim ne toke	m ³	5,190.00		
4	2.47/an	Germim shkemb mesatar me cekic me ekskavator me zinxhir	m ³	8,100.00		
5	2.48/an	Germim shkemb i forte me cekic me ekskavator me zinxhir	m ³	3,200.00		
6	3.158/1a	Transport me auto deri 1.0 km	m ³	4,800.00		
7	3.158/2a	Transport me auto deri 2.0 km	m ³	8,160.00		
8	3.158/5a	Transport me auto deri 5.0 km	m ³	7,000.00		
					Shuma I	
		II - Shtresat rrugore				
1	3.211	Shtrese çakelli mbeturine kave t= 20 cm, perhapur e ngjeshur makineri	m ²	80,000.00		
2	3.208	Shtrese çakelli t=10cm, Makadam perhapur e ngjeshur me makineri	m ²	80,000.00		
3	3.212/c	Shtrese stabilizant t=15cm	m ²	111,000.00		
4	3.222/2	Shtrese binderi me granil gure kave,6 cm, me makineri	m ²	92,000.00		
5	3.226/1	Shtrese asfaltobetoni me granil gure kave ,4 cm me makineri	m ²	92,000.00		
					Shuma II	
		III- Punime Vepra Arti LOTI II				
		A - Mure mbajtese dhe pritese				
1	3.68/a	Germim themel (gropa) sip10-30m ² , shkemb bute,h= 2.5 m, makineri,	m ³	5,980.00		
2	3.183/a	Shtrese zhavor lumi t=10cm	m ²	8,100.00		
3	3.240	Struktura monolite betoni C 12/15 per shtresa nen themel	m ³	1,287.00		
4	An-8	Mbushje me cakell pas mureve	m ³	2,880.00		
5	3.243	Struktura monolite betoni C 16/20	m ³	2,620.00		
6	3 an/1t	Tubate brinjezuar Hdpe SN8 Ø= 315 mm ne gjatesine e rruges	ml	12,800.00		
7	An-48	Prishje struktura prej guri (mure guri)	m ³	127.00		
					Shuma A	
		B - Ndertimi Tombinove rrethore				
1	3.68/a	Germim themel (gropa) sip10-30m ² , shkemb bute, h= 2.5 m, makineri	m ³	925.00		
2	3.183/a	Shtrese zhavor lumi t=10cm	m ²	912.00		
3	An-8	Mbushje me cakell	m ³	812.00		
4	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	550.00		
5	3.240	Struktura monolite betoni C 12/15 (Këmish për tubat)	m ³	387.00		
6	3.243	Struktura monolite betoni C 16/20 (pusetat, muret mbajt.)	m ³	511.00		
7	3.761	Beton C 25/30, me beton pompe ~ 30 m ² (torkret në dalje)	m ³	244.00		
8	3.289	F.V. Hekur periodik Ç-5, Ø>12mm	ton	21.00		
9	An.18	Guardrail H2 anesore per ure me 2 valez. ne 1 ane ,W4 + aksesoret	ml	800.00		
					Shuma B	
		C - Bordura, Kuneta				
1	3.244	Struktura monolite betoni C 20/25 per kuneten anesore	m ²	1,200.00		
					Shuma C	
					Shuma III (A+B+C)	
		IV-Hekur				
1	3.289	F V hekur betoni periodik, Ç - 5, Ø > 12mm	ton	38.00		
					Shuma IV	

		V-Sinjalitika LOTI II				
1	An106	Tabela trekendore normal me A = 90	cope	49.00		
2	An103	Tabele rrethi "ndalim" normal me D = 60	cope	11.00		
3	An91	Panele plotesues I sinjalistikes rrethore normal 50x25	m²	8.00		
4	An59	Sinjale "emër rruge" LxH normal 80x25	m²	7.00		
5	An1	Guardrail- N2 anesore me 2 valez. ne 1 ane , W2 + aksesori	ml	1,000.00		
6	An124	Vijezi shiriti gjatesor dhe anesor me gjeresi 12 cm, Akrelike	ml	46,342.55		
7	An119	Pervijues modular te kthesave (qfte)	cope	39.00		
Shuma V						
Shuma I ÷ V						
VLERA PA TVSH						
FONDI REZERVE 5%						
VLERA PA TVSH						
TVSH 20%						
VLERA TOTALE NE LEKE						

STUDIO E PROJEKTIMIT
NG STRUCTURES SHPK

MIRATOI
KRYETARI I BASHKISË
ADRIATIK ZOTKAJ