

Preventiv

Objekti: RIKONSTRUKSIONI I RRUGES BABUNJE - AGIM (B = 6.5M)

Nr.	Analiza	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (lek)	SHUMA (lek)
A		PUNIME PER EVADIMIN E MBETURINAVE DHE REHABILITIM TE ZONAVE KU JANE PRISHUR NDERTESAT DHE GJELBERIMI				
		A-1. Punime dheu dhe transport mbeturinash				
1	3.17	Germime dheu ne seksion te lire me krahe,ne toke te bute,kateg.I-II, pa hedhje	m ³	950.0		
2	An-49	Prishje struktura prej betoni	m ³	250.0		
3	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	6,554.0		
4	An-4	F.V. Peme dekorative varieteti olivio lecino ne vazo 26 litershe, perimenter 14-16 cm	cope	179.0		
		Shuma A-1				
					Shuma A	
B		PUNIME PER NDERTIMIN E RRUGES DHE SHETITORES				
		B-1 Rruge dhe Sheshe				
1	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , toke zak, kategoria III, me shk ne toke	m ³	5,604.0		
2	3.An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	16,389.1		
3	3.618	F V bordura betoni 20x35 cm	ml	1,400.0		
4	3.616	F.V Bordura betoni 12x25 cm	ml	100.0		
5	2.262/4	Shtrese betoni C 16/20	m ³	144.0		
6	2.262/3	Shtrese betoni C 12/15	m ³	140.0		
7	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	1,400.0		
8	3.212/b	Shtrese stabilizant t=10cm	m ²	29,575.0		
9	3.229/2	Shtrese binderi 6cm	m ²	25,025.0		
10	3.231/1	Shtrese asfaltobetoni me zall lavatrice, 3cm, me makineri	m ²	25,025.0		
11	3.244/1	Struktura te holla monolite betoni C 20/25 (KANALET+KUNET+MBISTRUKTURA E VEPRAVE TE ARTIT ETJ)	m3	1,540.0		
12	3.244	Struktura monolite betoni C 20/25 (KONTRABORDURE 0+00-0+700 DHE SHTESAT E TOMBINOVE ETJ)	m3	148.0		
13	2.167	F V hekur betoni i zakonshem	ton	25.5		
14	An-4	Mbushje stabilizant bankina	m ³	455.0		
		Shuma B-1				
		B-2 Punime Elektrike				
1	An-M3	F V shtylla dekorative dy degeshe per ndriçim, H=8m,	cope	38.0		
2	An-3	FV ndricues LED 120 wat dhe 75 Wat	cope	38.0		
3	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	38.0		
4	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	38.0		
5	An- M3	F V kuader komandimi komplet me santeri+fotoelement	cope	2.0		
6	An-56	F.V. Tuba metalik D=140mm	ml	20.0		
7	An-1	F.V. Kabell XYMM 0.6/ 1KV. 3x2.5mm2	ml	304.0		
8	An-2	F.V. Kabell FG7OR 0.6/ 1KV. 5x 25mm2	ml	800.0		
9	3.654/1	Furnizim, vendosje tuba plastmasi ø 80	ml	800.0		
10	3.182/a	F.V. Rere	m ²	162.0		
		Shuma B-2				

C		PUNIME PER KUSH				
1	3.379	F.V. Rere nen dhe mbi tubacione PE + kompaktesim	m³	20.0		
2	An-9 M3	F.V. Zhavorr ne kanale + ngjeshje me shtresa cdo 25cm	m³	560.0		
3	2.523/1	F.V tuba l brinjezuar HDPE Ø 200 mm	ml	182.0		
4	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	1,400.0		
5	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	162.0		
6	An - 23	Pusetete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	56.0		
					Shuma C	
D		PUNIME PER SINJALISTIKEN				
1	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	1,938.0		
2	An99	Tabele sinjalizimi	cope	40.0		
3	An22	Guardrail H2 anesore per ure me 2 vale ne 1 ane+handrail ,W5 + aksesoret	ml	80.0		
4	An151	Vizime me boje bikomponente	m2	1,150.0		
					Shuma D	
			SHUMA (A - C)			
			T.V.SH. 20%			
			VLERA NE TOTAL			

