

PREVENTIV- ZBATIMI

PROJEKTI:Rikonstrukcion Rruge. Unaza Lumalas - Melçan - Porodinë						
Nr	Nr Analiz	Pershkrimi i zerit	Njesi	Sasia	Cmimi	Shuma ne Lek
I - PUNIME PER TRUPIN E RRUGES AKSI LUMALAS - MELÇAN (0+000 - 1+560)						
1	3.98/b	Germim toke e zakonshme,seksion i lire	m³	1,129.0		
2	AN-1	Frezim shtrese asfalti me makineri	m²	5,460.0		
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m³	264.0		
4	3.212	Shtrese cakulli 15 cm, makadam, përhapur e ngjeshur makineri	m²	2,496.0		
5	3.212/b	Shtrese stabilizant t=10 cm	m²	2,340.0		
6	3.212/b	Shtrese stabilizant t=10 cm (bankinat)	m²	780.0		
7	3.222/1	Shtrese binderi me granil gur kave,5 cm,me makineri	m²	1,560.0		
8	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4 cm, me makineri	m²	7,020.0		
9	3.158/1a	Transport dheu me auto deri 1.0 km	m³	1,129.0		
Shuma I						
II - PUNIME PER TRUPIN E RRUGES AKSI MELÇAN - PORODINE (1+560 - 3+600)						
1	3.98/b	Germim toke e zakonshme,seksion i lire	m³	4,635.0		
2	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m³	1,163.0		
3	3.212	Shtrese cakulli 15 cm, makadam, përhapur e ngjeshur makineri	m²	11,424.0		
4	3.212/b	Shtrese stabilizant t=10 cm	m²	11,220.0		
5	3.212/b	Shtrese stabilizant t=10 cm (bankinat)	m²	2,040.0		
6	3.222/1	Shtrese binderi me granil gur kave,5 cm,me makineri	m²	9,180.0		
7	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3 cm, me makineri	m²	9,180.0		
8	3.158/1a	Transport dheu me auto deri 1.0 km	m³	4,650.0		
Shuma II						
III - VEPRAT E ARTIT						
a) Muret betoni C20/25						
1	2.262/3	Shtrese betoni C 12/15	m3	1.0		
2	3.244	Struktura monolite betoni C 20/25, muret	m3	9.0		
3	2.167	F V hekur betoni periodik Ø > 12 mm	ton	0.6		
4	3.654	Tuba drenimi PVC D=100 mm	ml	10.0		
Total a)						
b)Tombino BOX (2x2 dhe 5x3)						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m³, ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m³	140.0		
2	3.183/a	Shtrese zhavor lumi t=10cm	m2	30.0		
3	An-9 Ref.M3	Mbushje me zhavorr per tombino	m3	14.4		
4	2.262/3	Shtrese betoni C 12/15	m3	20.0		

5	3.247	Beton strukturash C 25/30.	m3	112		
6	3.624	H / Izolim me emulsion, 2 duar bitum	m2	129.0		
7	2.167	F V hekur betoni periodik Ø > 12 mm	ton	10.1		
Total b)						

c)Tombino rrethore						
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m³, ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m³	165.0		
2	An.164/1b	Mbushje me cakell e gur gurore perhapur e ngjeshur me makineri (mbushje bazamenti + mbushje pas tombinos)	m³	79.0		
3	3.363	Tombino me tuba betoni Ø 400, mbi shtrese betoni	m	29.0		
4	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	73.5		
5	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	ml	11.5		
6	3.244	Struktura monolite betoni C 20/25 (mbrojtje tombino, portalet)	m³	99.4		
7	2.167	F V hekur betoni periodik Ø > 12 mm	ton	3.6		
8	3.158/1a	Transport dheu me auto deri 1.0 km	m3	165.0		
					Total c)	
Shuma III						
IV - PUNIME SINJALISTIKE						
1	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	7,200.0		
2	An151	Vizime me boje bikomponente (vizime kembesoresh, shigjeta drejtimi etj)	m²	10.0		
3	An50	Tabele drejtkëndore (tregimi)(AxB) e zvogëluar 40x60 (shenja ure)	cope	4.0		
4	An158	FV tabela te ndryshme rrugore D=60cm	cope	7.0		
5	An105	Tabela trekendore e vogel me A = 60	cope	9.0		
6	An63	Sinjalet e drejtimit urban HxL e vogël 20x100	cope	5.0		
7	An97	Tabela tetekendore normal me A-B, 90-30 (STOP)	cope	12.0		
8	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	24.0		
Shuma IV						
SHUMA TOTALE (I-IV)						
Fondi rezerve 2%						
SHUMA						
T.V.SH 20 %						
SHUMA						