

MIRATOT
KRYETARI BASHKISE PIRENJAS
Z.NURI BELBA

PREVENTIV
"RIKONSTRUKSION RRUGËS RASHTANIT "BASHKIA PIRENJAS"

GJATESIA TOTALE (1775) ML
Gjeresia Asfaltike 3.5 ML

SEGMENTI NR 1						
Nr	Nr analiz	EMERTIMI I PUNIMIT	Nesia	Sasia	Cmimi	Vlera
I-PUNIME GERMIMI						
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	1,500		
2	3.25/c	Germim me krahe seksion detyruar me gjeresi b > 1 m, h=1.5 m, toke e forte.	m3	50		
3	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m3	15.981		
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	1,500		
SHUMA I						
II_1-PUNIME URE DHE KANALI NE FILLIM						
1	3.244/1	Beton C20/25 per kanalin ne fillim te rruges	m3	20		
2	3.287	F V hekur betoni i zakonshem Ø 6	ton	0.4		
3	3.248	Struktura monolite betoni me çakell C 30/37	m3	13		
4	3.289	F V hekur betoni periodik, Ç - 5, Ø > 12mm	ton	1.3		
SHUMA II						
II_2-PUNIME BETONI ,GURI DHE TOMBINO						
1	3.244/1	Beton C20/25 per mure anesore mbajtes	m3	388		
2	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	3		
3	2.166	F V hekur betoni periodik Ø > 10 mm	ton	2.81		
4	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	14		
5	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	40		
6	3.240	Struktura monolite betoni C 12/15 (per kanal dhe kunet)	m3	278		
7	An-57	F.V. Tuba metalik D=219mm	ml	60		
8	An - 22	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	3		
9	3.333	Gabiona me rrjete teli te zinguar, gure kave 1x1x2 m	m3	70		
SHUMA II						
III-PUNIME SHITRESASH						
1	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri t=20cm(Gjeresia 5m)	m3	1330		
2	3.212/b	Shtrese stabilizant t=10cm	m2	6212.5		
3	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	6212.5		
4	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	6212.5		
Lagja e Pusanikeve						
1	3.212/b	Shtrese stabilizant t=10cm	m2	260		
2	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	260		
3	3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	260		

Ing. Kastriot Begaj
Projektim - Zbatim
Zgjidhje - Kolaudim
Projekt - Zjarrfikes

13/07

		SHUMA III				
IV-PUNIME PER NDRICIMIN RRUGOR						
1	3.An/53	F V shtylla metalike per ndricim, H=7m, d=160mm	cope	44		
2	3.An	FV ndricues Smart VP CL1 CR M-S 250W GG FAE 44004,me llampe 250W 230V	cope	44		
3	3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	44		
4	3.An/et	FV elektroda tokezimi te xingura 50x3mm, L=150cm	cope	44		
5	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	44		
6	2.262/3	Shtrese betoni C 12/15	m3	16		
7	4.131/3.5	F.V. Kabell 0,6/1 KV ; tip RG7R ; 4x10mm2	m	1910		
8	4.131/3.5	F.V. Kabell 0,6/1 KV ; tip RG7R ; 4x10mm2(Per lagjen e Pusani	m	690		
9	4.149/2	F.V. percjellsa cute izoluar me gome per ndricim ne tubo te vendosura me pare,seksion 1,5 mm2	km	0.22		
10	An	F V kuader komandimi komplet me santeri+fotoelement	cope	1		
11	An+2,523	Tub pvc Ø 200 (inkastrimin e shtylles)	ml	22		
		SHUMA IV				
V-PUNIME TE NDRYESHME+SINJALISTIKA						
1	3.212/b	Shtrese stabilizant t=10cm (BANKINE)	m2	1755		
2	An158	FV tabela te ndryshme rrugore D=60cm	cope	2		
4	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt)	ml	2510		
5	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	50		
		SHUMA V				
		SHUMA I-VI				
		Fond rezerve 3%				
		SHUMA PA TVSH				
		T.V.SH. 20%				
		TOTALI				

Projektoi
Kastriot Begaj

Ing. Kastriot Begaj
Projektim - Zbatim
Mekaynje - Kolaudim
Rregullim - Zjarrfikes

[Signature]