

REPUBLIKA E SHQIPERISE
BASHKIA SELENICË



PREVENTIV: SHTEGU UJVARËS RASALIT

NR	NR/AN	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA
HAPJE SHTEGU						
1	2.1a	Germim dheu me krahe transport k dore 10m, kat IV	m3	490.0		
2	3.2	Prerje bime te vogla ø ~ 10cm	m2	17,000.0		
3	3.7	Shkulje rrenjeve bimeve te vogla	m2	20,318.6		
4	3.3	Preje e sistemit pemesh ø 10 - 20 cm	cope	20,000.0		
5	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri(t=30cm)	m3	1,680.0		
6	2.262/4	Shtrese betoni C 16/20	m²	240.0		
7	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	6.00		
8	3.922/3	F.v. Tabele drejtkëndore (tregimi)(AxB) e madhe 135x200	cope	3		
9	3.922/1	F.v. Tabele drejtkëndore (tregimi)(AxB) e vogel 60x90	cope	10		
10	3.923/1	F.v. Tabele katërkëndore "sherbimi" normal 60x90	cope	2		
11	3.921/1	F.v. Tabele katrore normal me A=60	cope	20		
12	1.99/p	Pergatitje konstruksione metalike te perbera	ton	2.20		
13	an.	Litar per parmaket metalik	ml	4100		
3	an.	Transport materiale me kafshe, deri 5 km	ton	100		
3	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	20		
URAT						
1	1.99/p	Pergatitje konstruksione metalike te perbera	ton	4.30		
2	an.	Transport materiale me kafshe, deri 5 km	ton	4.3		
2	3.636	Parmake ure, metalik i gatshem.	kg	2420		
PISHINA						
1	2.54/2	Mur guri ne lartesi deri 3m me llaç çimento M 25	m3	140		
2	1.99/p	Pergatitje konstruksione metalike te perbera	ton	0.50		
3	an.	Transport materiale me kafshe, deri 5 km	ton	5		
6	2.262/4	Shtrese betoni C 16/20	m²	50.0		
7	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	3.00		
BALLKONI (BALLKON METALIK + PERPUNIM SHKEMBI)						
1	1.99/p	Pergatitje konstruksione metalike te perbera	ton	3.00		
2	an.	Transport materiale me kafshe, deri 5 km	ton	3		
3	2.201	Themel betoni C16/20	m3	0.70		
13	an.	Litar per parmaket metalik	ml	9		
13	3.733	Germim shkambi me matrapik ne tunele me seksion ~ 5 m2	m3	2		
AMBIENTE REKREATIVE + SINJALIZYKË (2 Cezma + 10 stola)						
1	2.1a	Germim dheu me krahe transport k dore 10m, kat IV	m3	2.0		
2	2.54/2	mur guri lartesi deri 3 m	m3	1.4		
3	2.262/4	shtrese betoni c 16/20	m3	1.0		
4	2.355/b	veshje me pllaka guri	m2	3.0		
5	2.491/b	F.V Tuba e rakorderi ujesjellesi PE d=25mm, t = 2.0 mm, PN 10	mi	200.0		
6	an.	Transport materiale me kafshe, deri 5 km	ton	6		
6	an.	stola druri + transport me kafshe	cope	30		
SHUMA TOTALE 1,2,3,4,5						
TVSH 20%						
SHUMA TOTALE ME TVSH						

HARTOI

Ing. Klevis BEDINAJ

Ark. Fatjon DEVOLLAJ

Ark. Tea HAXHIAJ

Ark. Sara BREGU

Ark. Katerina TRALO

Ark. Olta HASIMAJ

MIRATOK
KRYETARI
Nertil BEJLALAJ

