

Objekti: Rikonstruksion rruga "XHEVDET HAFIZI"

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA
1. PUNIME GERMIMI				
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	550
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	550
		SHUMA 1:		
2. PUNIME SHITESH				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	332
4	3.212/b	Shtrese stabilizant t=10cm	m2	2215
		SHUMA 2:		
3. ANALIZA TEKNIKE				
5	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	2215
6	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m2	2215
7	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	24
8	An.5	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	490.0
9	3.616	F V bordura betoni 12x25cm	ml	106
10	2.262/4	Shtrese betoni C 16/20, kunete	m3	26

Objekti: Rikonstruksion rruga tek pallatet Nis-Cigares, NISHTULLA

1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	450
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	450
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	211
4	3.212/b	Shtrese stabilizant t=10cm	m2	1405
5	2.262/4	Shtrese betoni C 16/20, per rrugen t=15cm	m3	211
5	2,166	F V hekur betoni periodik Ø 6 - 10 mm	ton	3.7
		SHUMA1 :		
2. ANALIZA TEKNIKE+ PUNIME TROTUARI				
1	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	47.4146
2	3.212/b	Shtrese stabilizant t=10cm	m2	316
3	2.262/4	Shtrese betoni C 16/20, per rrugen t=15cm	m3	48
4	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	15

5	An	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	350.0
6	3.616	F V bordura betoni 12x25cm	ml	300
7	2.262/4	Shtrese betoni C 16/20, kunete	m3	20
5	2,166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.82

Objekti: Rikonstruksion rruga "PJETER BUDI"

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSI A	SASIA
		1. PUNIME GERMIMI		
1	3.89/a	Germim dheu me ekskavator goma 0.25 m³, ne kanale gjeresi deri 2 m, token zak, kategoria III, me shk ne mjet	m3	250
2	3.158/5 a	Transport dheu me auto deri 5.0 km	m3	250
		SHUMA 1:		
		2. PUNIME SHTRESASH		
3	3.164/1 b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	136
4	3.212/b	Shtrese stabilizant t=10cm	m2	905
		SHUMA 2:		
		3. ANALIZA TEKNIKE		
5	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	905
6	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m2	905
7	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	24
8	An	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	372.0
9	2.262/4	Shtrese betoni C 16/20, kunete	m3	27

Objekti: Rikonstruksion rruga "Llogaraja"

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia
A-1		Punime Germimi dhe Mbushje ne Rruge		
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m³, ne kanale gjeresi > 2 m, token zak, kategoria III, me shk...	m³	288.00
2	3.158/5 a	Transport dheu me auto deri ne 5 km	m³	288.00
3	3.198	Cilindrim kasonete me rul	m²	1,152.00

			Shuma	A-1	
--	--	--	--------------	------------	--

A-2	Punime Shtresa rrugore				
1	3.212	Shtrese çakelli t=10/15cm, makadam, perhapur e ngjeshur me makineri	m2	1,152.00	
2	3.212/c	Shtrese stabilizant t=15cm	m ²	1,152.00	
3	2.262/4	Shtrese betoni C 16/20	m ³	230.40	
4	3.287	F V hekur betoni i zakonshem Ø 6~ 10mm	ton	9.20	
5	2.262/4	Beton C 16/20 (per kanal prites ne fund te rruges 30x30)	m ³	0.48	
6	2.617	F.V. kapak metalik + zgare ne vrima ventilimi 20x15cm	cope	1.00	

Objekti : Rikonstruksion sheshi tek pallati Jedas

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia
A-1	Punime Germimi dhe Mbushje ne Rruge			
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk...	m ³	450.00
2	3.158/5a	Transport dheu me auto deri ne 5 km	m ³	450.00
		Shuma	A-1	

A-2	Punime Shtresa rrugore				
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	280	
4	3.212/b	Shtrese stabilizant t=10cm	m2	1864	
3	2.262/4	Shtrese betoni C 16/20, t= 12cm	m ³	71.00	
4	3.287	F V hekur betoni i zakonshem Ø 6~ 10mm	ton	1.40	
5	2.262/4	Beton C 16/20 (kunete)	m ³	17.00	

			Shuma	A-2	
		3. ANALIZA TEKNIKE			
5	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	1275	
6	3.233/1	Shtrese asfaltobetoni me zall lavatrice,4cm,me mak	m2	1275	
7	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	15	
8	An	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	490.0	
9	3.616	F V bordura betoni 12x25cm	ml	106	
		SHUMA 3:			

Objekti: Rikonstruksion sheshi plazh

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia
A-1	Punime Germimi dhe Mbushje ne Rruge			
1	3.98/b	Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, token zak, kategoria III, me shk...	m ³	351.11
2	2.426/3	Prishje shtresa betoni	m ³	12.0000
3	3.158/5a	Transport dheu me auto deri ne 5 km	m ³	350.00
		Shuma	A-1	
A-2	Punime Shtresa rrugore			
3	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri, t=15	m3	209
4	3.212/b	Shtrese stabilizant t=10cm	m2	1780
5	2.262/4	Shtrese betoni C 16/20	m ³	208.00
6	3.287	F V hekur betoni i zakonshem Ø 6~ 10mm	ton	1.70
		Shuma A-2		
		3. ANALIZA TEKNIKE		
7	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	12
8	An	F V tuba te brinjezuar HDPE SN8 d=250 mm	ml	210.0
		SHUMA 3:		