

PREVENTIV

**OBJEKTI : INVESTIME NE KUADER TE PROJEKTIT BASHKI TE ZGJUAR/
RR "LIN DELIA"**

Nr	Nr.An.	EMERTIMI	Njesia	Sasia
1	3.167	FV shtylla metalike konike ndricimi H=9m PAICC-3	cope	7
2	AN-E1	F.V. Ndrices projektor LED 80W, 4000K	cope	7
3	3.168	F.V. krah shtylla metalike KRH - MSI 1500/1500/10	cope	7
4	AN-E2	F.V. Tub fleksibel D=90mm, dy shtresor	m	242
5	3.590	F.V. Pusete betoni me kapak gize dhe gjithë aksesoret +tokezuesit 40x40x40	cope	9
6	AN-E3	Demontim shtylle ndricimi	cope	10
7	AN-E4	F.V. Kabllo TU Cu, FROR 3x1.5mm ²	m	84
8	4.131/3.5	F.V.ne toke kablllo Cu fuqie ±1000V, me izolim gome e mbulese plastmasi, te armuar, 4x10mm ²	m	299
9	3.172	F.V. kuader komandimi komplet me fotoelement	cope	1
10	3.182	FV elektroda tokezimi te xingura 50x3mm L=150cm	cope	7
11	2.500	F.V. Percjelles Tokezimi , Cu, S=35mm ² , i zhveshur	m	21
12	3.243	Struktura monolite betoni C 16/20	m ³	1.75
13	2.150	Germim e mbushje dheu me krah per kanale kategori III, h=1.5m	m ³	96.8
14	2.426/3	Prishje shtresa betoni	m ³	5.8
15	2.37/5a	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	96.8
16	3.969	Skarifikim shtrese asfalti me makineri	m ²	16.8
17	4.190	Prerje asfalti me disk, ne te dy anet.	ml	42
18	3.711	Shtrese Stabilizanti 8 cm	m ²	16.8
19	3.228	Shtrese binderi me zall lavatrice, 4cm, me krah	m ²	16.8
20	3.233	Shtrese asfaltobetoni me zall lavatrice,4cm,me krah	m ²	16.8
21	2.262/4	Shtrese betoni C 16/20	m ³	5.5
22	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	97
SHUMA I				
Fondi Rezerve 5%				
SHUMA II				
TVSH				
T O T A L I				

preventivoi: Ing. Elsid Sadiku

A ENERGJIE

[illegible]