

**PREVENTIV PUNIMESH**

**OBJEKTI: NDERTIM URE BETON ARME FSHATI KETE, NJESIA ADMINISTRATIVE XIBER, BASHKIA KLOS**

| <b>Nr</b> | <b>Nr.An</b> | <b>Emertimi Punimeve</b>                                                                                               | <b>Njesia</b>  | <b>Sasia</b> | <b>Cmimi</b> | <b>Vlera</b> |
|-----------|--------------|------------------------------------------------------------------------------------------------------------------------|----------------|--------------|--------------|--------------|
| <b>A</b>  |              | <b>Punime germimi dhe mbushje</b>                                                                                      |                |              |              |              |
| 1         | 3.87/b       | Germim dheu me ekskavator goma, 0.25 m <sup>3</sup> , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke | m <sup>3</sup> | 306.00       |              |              |
| 2         | 3.128/b      | Germim shkemb i coptuar me ekskavator 1.0 m <sup>3</sup> , shkemb, ne themele gjeresi >2 m, me shkarkim ne mjet        | m <sup>3</sup> | 124.00       |              |              |
| 3         | An.1         | Largimi i ujerave nga themelet me sistemin wellpoint                                                                   | op             | 346.00       |              |              |
| 4         | 3.396/1      | Mbushje me zhavorr/cakell pas shpatullave                                                                              | m <sup>3</sup> | 150.0        |              |              |
| 5         | 3.164/1b     | Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri                                     | m <sup>3</sup> | 254.00       |              |              |
| 6         | 3.158/5a     | Transport dheu me auto deri 5.0 km                                                                                     | m <sup>3</sup> | 124.00       |              |              |
|           |              | <b>Shuma A</b>                                                                                                         | <b>leke</b>    |              |              |              |
| <b>B</b>  |              | <b>Punime betoni dhe betonarme</b>                                                                                     |                |              |              |              |
| 1         | 3.240        | Struktura monolite betoni C 12/15, per nenshtrese                                                                      | m <sup>3</sup> | 2.20         |              |              |
| 2         | 3.245        | Struktura monolite betoni C 25/30, per themel                                                                          | m <sup>3</sup> | 14.72        |              |              |
| 3         | 3.245        | Struktura monolite betoni C 25/30, per ballnat                                                                         | m <sup>3</sup> | 24.12        |              |              |
| 4         | 3.245        | Struktura monolite betonarme C 25/30, per brezin                                                                       | m <sup>3</sup> | 2.07         |              |              |
| 5         | 3.245        | Struktura monolite betonarme C 25/30, per soleten                                                                      | m <sup>3</sup> | 5.70         |              |              |
| 6         | 3.245        | Struktura monolite betoni C 25/30, per shpatullat                                                                      | m <sup>3</sup> | 96.00        |              |              |
| 7         | 3.289        | F.V. Hekur betoni periodik, Ç- 5, Ø > 12mm                                                                             | ton            | 2.24         |              |              |
| 8         | 3.624        | H / Izolim me emulsion, 2 duar bitum                                                                                   | m <sup>2</sup> | 152.00       |              |              |
|           |              | <b>Shuma B</b>                                                                                                         | <b>leke</b>    |              |              |              |
|           |              | <b>Shuma pa T.V.SH (A+B)</b>                                                                                           | <b>leke</b>    |              |              |              |
|           |              | <b>T.V.SH 20%</b>                                                                                                      | <b>leke</b>    |              |              |              |
|           |              | <b>Shuma me T.V.SH</b>                                                                                                 | <b>leke</b>    |              |              |              |

**PREVENTIVUES**

**"TRIANGLE" SH.P.K**

Ing. Zenulla Mehmeti