

**GRUMBULLIMI I VENDBURIMEVE UJORE PER FURNIZIMIN ME
FSHATIT BERZESHTE BASHKIA PRRENJAS**

NR.	ANALIZES	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI
A. Punime Ndertimi per Kaptazhin					
1	3.90/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, prani uji, kategoria III, me shk ne mjet	m ³	280	
2	2.262/3	Shtrese betoni C 12/15	m ³	13.5	
3	3.247	Struktura monolite betoni me çakell C 25/30	m ³	45	
	2.195	Hidroizolim me emulsion dhe dy duar bitum	m ²	90	
4	2.258	Nenshtrese zhavori	m ³	28	
5	An-9	Mbushje me zhavorr pas mureve	m ³	45	
6	3.644	F.V. Porte metalike (1.4 m ²)	ton	0.16	
7	3.287	F.V. Hekur per armim (S 500)	ton	3.5	
8	2.538	F.V. pjese speciale celiku Ø=90 te pa izoluar per ujesjellsa te jashtem (bryla, Tee, qafore, etj)	ton	0.04	
9	2.494/5	F.V saracineska bronzi Ø 2 " = 50 mm	cope	2	
10	3.837	Rrethim me kollona b/a + rrjete teli	m ²	240	
11	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m ³	380	
12	An HE	Porte hyrese brenda rrethimit per kembesoret	m ²	5	
SHUMA A					
SHUMA B					
C. Punime Ndertimi për linjen e jashtme					
1	2.182	Konstruksione metalike te thjeshta (per shkalle hyrëse ne depo)	ton	0.05	
2	3.183/a	Shtrese zhavor lumi t=10cm	m ³	220	
3	3.101/a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne toke	m ³	3900	
4	2.491/f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, t = 4.7 mm, PN 10	ml	4500	
5	2.261	Shtrese rere	m ³	458	
6	2.19	Hedhje, rrafshim, mbushje dheu me krah, kategoria III	m ³	1580	
7	2.491/a	F.V Tuba e rakorderi ujesjellesi PE d=20mm, t = 2.0 mm, PN 10	ml	550	
8	An - 20	Pusete b/a, 80 x 80 cm, h = 150 cm	cope	12	
9	An - 18	Pusete shkarkimi b/a, 50 x 50 cm, h = 100 cm	cope	22	
10	2.130/1a	Mure b/a t = 21-30cm, h ~ 4m C 20/25	m ³	41	
11	2.494	F.V saracineska bronzi Ø 1/2 " = 15 mm	cope	128	
12	2.494/6	F.V saracineska bronzi Ø 2 1/2 " = 70 mm	cope	16	
13	3.247	Struktura monolite betoni me çakell C 25/30 (bazamenti)	m ³	36	

14	3.249	F V soletone b/a C 16/20	m ³	7.5	0
15	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	11.6	0
16	3.628	Lluster cemento 2 cm 1: 2	m ²	105	0
SHUMA C/I					-
SHUMA D					-
SHUMA (A+B)					-
Fond Rezerve 5%					-
SHUMA					-
SHUMA (A+B + TVSH 20%)					-
SHUMA					-

" HE & SK 11 "
Ing. Festim BREGASI

Festim Bregasi



Mikato:
Exyefari e Bashkise
Mikato Rina