



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr Prot. Kamez me / /2018

OBJEKTI: RRUGA "SHEBENIKU" LAKNAS

L=1730ml, B=5m basf=4m+0.5*2 bankine						
Nr	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
A		PUNIME NE RRUGE				
1	3.139	Germim i dheut me eskavator me goma kat. III	m ³	865		
2	3.158/5a	Transport dheu me auto 5km	m ³	865		
3	3.353	Mbushje me cakull shkembor+bankine	m ³	1730		
4	3.158/5a	Transport cakull me auto 5km	m ³	1730		
5	3.208	Shtrese cakulli T=10cm +bankine	m ²	8650		
6	3.212/b	Shtrese stabilizanti t=10 cm +bankine	m ²	8650		
7	3.229/1	Shtrese binder t=5 cm	m ²	6920		
8	3.231/1	Shtrese asfaltobetoni t=4 cm	m ²	6920		
9	An.	Ngritje pusete	cope	34		
10	An.	Spostim shtylla centrifugale betoni	cope	2		
11	2.426/2	Prishje mure blloqe + transport	m ³	35		
12	An.96	Tabele sinjalistike 60-90cm	cope	2		
		SHUMA I				
L_{total}=1017ml (L₁ = 110ml, B = 16 m, b = 10asf+2x0.5kunete+2x2.5trotuar),(L₂ = 370ml, B = 11						
Nr	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
B		PUNIME NE RRUGE				
1	3.229/1	Shtrese binder t=5 cm	m ²	1488		
2	3.231.1	Shtrese asfaltobetoni 1x4 cm	m ²	6491		

3	An.	Spostim shtyllash	cope	5		
4	An.96	Tabele sinjalistike 60-90cm	cope	8		
5	3an43	Skarifikim asfalti	m ²	6491		
		SHUMA I				
II	PUNIME NE TROTUARE					
1	3.139	Germim dheu me eksavator	m ³	170		
2	3.158.5a	Transport dheu me auto 5 km	m ³	170		
3	3.353	Mbushje me cakull shkembi	m ³	195		
4	3.158.5a	Transport cakull shkembi	m ³	195		
6	3.617.1	F.V. bordure 15x35 cm	ml	1860		
7	2.111/2	Mure betoni C16/20 kontrabordure	m ³	150		
8	3.208	Shtrese cakull ne trotuar T=10cm	m ²	3179		
9	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	3179		
10	2.262/4	Shtrese betoni trotuari 10cm	m ³	255		
		SHUMA II				
III	PUNIME NE K.U.B					
1	3.139	Germim dheu me eksavator	m ³	650		
2	3.158.5a	Transport dheu me auto 5 km	m ³	650		
3	3.353	Mbushje me cakull shkembi	m ³	480		
4	3.158.5a	Transport cakull shkembi 5 km	m ³	480		
5	3.An.1t	F.V. Tubo brinjertzuar Ø 315 mm	ml	1883		
7	2.an.23	Puseta shiu me kapak gize 40x60, kapak gize	cope	64		
8	2.262.4	Shtrese betoni per kunete	m ³	99		
		SHUMA III				
IV	PUNIME PER NDRICIMIN					
1	3.654	F.V. Tub PVC Ø100 per telefonine	ml	930		
2	3.654	F.V. Tub PVC Ø100 per elektrikun, ndrçimin	ml	930		
3	3.an/1sh	F.V. Shtylla metalike konike ndrçimi H-9m PAICC-3	cope	28		

4	3.an/ksh	F.V. Krah shtylla metalike KRH-MSI 1500/1500/10	cope	28			
5	3.an	F.V Ndricues Smart VP CLI CR M-S 250W GG FAE44	cope	28			
6	An	F.V. morsete tre fazore +siguresa+kapak per shtyllen h=7	cope	28			
7	An	F.V Elektroda tokezim komplet l=150m	cope	28			
8	An	F.V Kabell TU me izolim PVC,tip XLPE 1(4x6mmk)	ml	465			
9	4.131/3.5	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x10mmk)	ml	465			
10	4.131/3.6	F.V Kabell Cu me me fuqi -1000V me izolim gome (4x16mmk)	ml	465			
11	An	F.V kabell tokezimi 1x3.5mmk	ml	45			
12	An	F.V kontaktor 3fazor aktiv me 4pole bobine 220V 40A	cope	2			
13	An-22/1	F.v puseta betoni me kapak gize 40x40 h=100cm	cope	28			
14	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	2			
15	An.	F.V kuader komandimi per ndriçim rrugor	cope	1			
16	An.	F.V kasete shperndarese	cope	1			
17	3.139	Germime dheu me ekskavator me goma	m ³	261.7			
18	3.158/5a	Transport dheu me auto 5km	m ³	261.7			
19	2.261	Mbushje me rere	m ³	112			
20	3/353	Mbushje me cakull shkembor (kanal)	m ³	148			
21	3/158/5a	Transport cakull me auto 5km	m ³	148			
		SHUMA IV					
V		PUNIME PER GJELBERIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VLERA	

<u>1</u>	An	F.V. Bordura betoni 0.6 x 0.2 x 0.8 ml	ml	372	
		SHUMA V			
		SHUMA I+II+III+IV+V			
		SHUMA A+B			
		T.V.SH 20%			
		TOTALI			

Preventivues:

Ing. Elmaz MURATI
 Ing. Flora MUÇA
 Ing. Hajredin MURGU

Drejtori i P.K.ZH.T-se

Ark.Arber Tola

MIRATOI
Xhelal MZIU

K R Y E T A R