



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ

Nr **Prot.**

Kamez me / /2018

OBJEKTI: NDERTIM TREGU KAMEZ						
OBJEKTI: TREGU KAMEZ (poste 146 cope)+(poste 68 cope)						
Nr	An.	Emertimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME PER NJE POSTE				
1	2.181	Konstruksion metalik I perbere(banaku)	ton	0.035		
2	4.125/1	Llamarine e zeze σ 10mm	kg	3.8		
3	2.279	Veshje me derrase , mashkull femer t=2.5cm	m ²	2.5		
4	2.401	Lyerje sipërfaqe metalike	m ²	1.2		
5	2.181	Konstruksion metalik I perbere(mbulesa)	ton	0.071		
6	4.125/1	Llamarine e zeze σ 10mm(mbulesa)	kg	35.3		
7	2.401	Lyerje sipërfaqe metalike(mbulesa)	m ²	3.2		
8	2. 1	Germim dheu kategoria e III me krah	m ³	0.200		
9	2.262/4	Themel + xokol C12/15	m ³	0.200		
6	3/208	Shtrese cakulli t=10cm	m ²	5		
7	3/212/a	Shtrese stabilizanti t=5cm	m ²	5		
8	An.	Shtrese me pllaka betoni	m ²	5		
		Shuma Per 1 poste				
		Total 214 poste	cope	214		
II		PUNIME NE SHESH				
1	3.139	Germim i dheut me eskavator me goma kat. III per nivelim	m ³	207		
2	3.158/5a	Transport dheu me auto 5km	m ³	207		
3	3.353	Mbushje me cakull shkembor +bankine	m ³	414		
4	3.158/5a	Transport cakull me auto 5km	m ³	414		
5	3.139	Germim i dheut me eskavator me goma kat. III per kanal per kub	m ³	60		
6	3.354	F.V tub Ø200 betoni	ml	300		
7	3.2An18	Pusete betoni 50x50x100	cope	5		
8	2.262.4	F.V. bordure 12x20 pergatitur ne vend	m ³	7.2		
9	An.	Shtrese me pllaka betoni	m ²	4140		
		Shuma II				
III		PUNIME NDERTIMI WC				
1	2/1.	Germim i dheut themel me krah	m ³	6.1		
2	2/111/2	Mur betoni themeli e xokol	m ³	10.4		
3	2/70/2	Mur tulle t=20cm	m ³	21		
4	2.158	Tra+kollona+solete betoni	m ³	35		
5	2.167	F.V hekur/beton $\geq$ 12	ton	5		
6	2.331	Suvatime te jashtme	m ²	126		
7	2.310	Suvatime te brendshme	m ²	162		
8	2.262.4	Veshje me pllake	m ²	151		
9	2.326	Shtrese betoni	m ³	5		

10	2.267/b	Shtrese me pllaka porcenalato gres	m ²	80		
11	2.375	F.v dritare duro/alumini	m ²	6.4		
12	2.395	F.v dyer duro/alumini	m ²	4		
13	2.196	Shtrese katrama	m ²	90		
14	2.462/4	Shtrese betoni mbi katrama t=6cm	m ³	4.5		
		Shuma III				
IV		PUNIME HIDROSANITARE+ELEKTRIKE				
1	2.5	F.V tuba rakorderi	kg	70		
2	2.494/2	F.V saracineske	cope	5		
3	2.495	F.V lavaman porcelanoz	cope	5		
4	2.504	F.V Wc allaturke	cope	12		
5	2/505	F.V Wc pisuar	cope	8		
6	2/508	F.V bolier	cope	2		
7	2/515	F.V pilete dysHEMEJE Ø50	cope	6		
8	2.480/2	F.V tub plasmasi Ø18-21	ml	80		
9	2.481/2	F.V percjelles PV500	ml	184		
10	2.483	F.V celsa, priza	cope	14		
11	2.498	Automat 24vend	cope	1		
		Shuma IV				
		SHUMA I -IV				
		T.V.SH.20%				
		TOTALI				

Preventivues:

Drejtori i P.K.ZH.T-se

Ing. Elmaz MURATI
Ing. Flora MUÇA
Ing. Hajredin MURGU

Ark.Arber Tola

MIRATOI
Xhelal MZIU

K R Y E T A R

