

PREVENTIV

OBJEKTI : SISTEMIM ASFALTIM RRUGA "FUNDI I BRINJES"

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
		Punime ne rrugen "FUNDI I BRINJES"				
		Punime ndertimi ne trup te rruges L=1865 m				
1	3.89/a + 3.158/a	Germim dheu me ekskavator 0.25 m³, toke zak, kategoria III, me shk ne mjet + Transport dheu me auto deri 5 km	m3	231.0	-	-
2	3.205/1	Shtrese zhavori lumi t=15cm, perhapur e ngjeshur me makineri	m2	7,525.0	-	-
3	3.212/b	Shtrese stabilizanti 10cm per rrugen	m²	6,530.0	-	-
4	3.212/b	Shtrese stabilizant t=10cm per bankine	m2	1,754.0	-	-
5	3.229/2	Shtrese binderi me zall lavatrice,6cm,me makineri	m2	6,543.0	-	-
6	3.244	Struktura monolite betoni C 20/25 (ura)	m3	5.0	-	-
7	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.22	-	-
8	AN	cmontim dhe montim parmakesh ekzistues	ml	10.00	-	-
		Shuma 1			-	-
		SHUMA			-	-
		TVSH 20%			-	-
		TOTAL			-	-

PREVENTIVOI
"Novatech Studio"shpk