



BASHKIA SHKODER

MIRATOHET

KRYETAR
VOLTANA ADEMI

PROJEKT-ZBATIM

PREVENTIV I PUNIMEVE

Objekti: "Projektim per objektin: Sistemim asfaltim Rruge te brendshme fshati "Samerisht I Vjeter" (Aksi nr.1)
Faza 1 Km 0+000-Km 0+620

Nr	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.89/b	Germim dheu	m ³	1.220		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1.220		-
3	An.164/1b	Mbushje me material shkembor	m ³	32		-
Shuma 1						-
2 - PUNIME PER TRUPIN E RRUGES						
1	An.164/1b	Mbushje me material shkembor	m ³	875		-
2	3.212/d	Shtrese stabilizant t=20 cm	m ²	2.515		-
3	3.222/1	Shtrese binderi, me granil gure kave , 5 cm, perhapur e ngjeshur me makineri	m ²	1.996		-
4	3.224/1	Shtrese asfaltobetoni me granil gure kave , 3 cm, perhapur e ngjeshur me makineri e ngjeshur me makineri	m ²	1.996		-
5	3.212/b	Stabilizant per bankine t=10cm	m ²	380		-
Shuma 2						-
3 - PUNIME NE TROTUAR,BORDURA,KUNETE						
1	An	F V bordura betoni 20x30 cm	ml	438		-
Shuma 3						-
4 - VEPRA ARTI						
1	3.89/b	Germim toke e bute seksion i lire + trans auto	m ³	98		-
2	3.240	Beton C 12/15 per kemishim tombinoje	m ³	24,1		-
3	3.365	Tombino betoni D=600 mm	ml	27		-
4	An-9	Zhavorr per nivelim	m ³	4,5		-
5	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	58,86		-
6	3,244	Beton C20/25	m ³	14		-
Shuma 4						-
5 - MURE MBAJTES						
1	3.89/b	Germim dheu	m ³	228		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	228		-
3	3,236	B/beton C 7/10 me 25% gur per mure mbajtes	m ³	166,4		-
4	An-8	Mbushje me cakell pas mureve	m ³	89		-
5	3,654	Furnizim, vendosje tuba plastmasi ø 100	ml	36		-
Shuma 5						-
6- PUNIME SINJALISTIKE						
1	An124	Vijejim shirita gjatesor dhe anesor me gjeresi 12 cm, Akrilike	ml	1.240		-
2	An144	Vizim Akrilik	m2	5,3		-
3	An97	F V tabela rrugore STOP	cope	3		-
4	An103	F.V. Tabela Rrethore D=60	cope	3		-
Shuma 6						-
7 - PUNIME NE KANALE						
1	3.89/b	Germim dheu per riprofilim kanalesh	m ³	101		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	101		-
Shuma 7						-
8 - PUNIME PRISHJE						
1	An-49	Prishje struktura prej betoni + trasport	m ³	2,9		-
Shuma 8						-
Total (1-8)						-
Fondi rezerve %			5%			-
Shuma pa TVSH						-
TVSH %			20%			-
Shuma me TVSH						-



InfraKonsult
Drejtuesi Ligjor
Ing. Redi STRUGA



BASHKIA SHKODER

MIRATOHET

KRYETAR
VOLTANA ADEMI

PROJEKT-ZBATIM

P R E V E N T I V I P U N I M E V E

Objekti: "Projektim per objektin: Sistemim asfaltim Rruge te brendshme fshati "Samerisht I Vjeter" (Aksi nr.3)
Faza 1 Km 0+000-Km 0+065

Nr	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.89/b	Germim dheu	m ³	220		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	220		
3	An.164/1b	Mbushje me material shkembor	m ³	4		
					Shuma 1	
2 - PUNIME PER TRUPIN E RRUGES						
1	An.164/1b	Mbushje me material shkembor	m ³	100		
2	3.212/d	Shtrese stabilizant t=20 cm	m ²	275		
3	3.222/1	Shtrese binderi, me granil gure kave , 5 cm, perhapur e ngjeshur me makineri	m ²	240		
4	3.224/1	Shtrese asfaltobetoni me granil gure kave , 3 cm, perhapur e ngjeshur me makineri e ngjeshur me makineri	m ²	240		
5	3.212/b	Stabilizant per bankine t=10cm	m ²	40		
					Shuma 2	
3 - PUNIME NE TROTUAR,BORDURA,KUNETE						
1	An	F V bordura betoni 20x30 cm	ml	72		
2	An	Spostimi i shtyllave elektrike ekzistuese	cope	1		
3	An	Spostimi i linjave elektrike ekzistuese	ml	10		
					Shuma 3	
4 - PUNIME SINJALISTIKE						
1	An124	Vijejim shirita gjatesor dhe anesor me gjeresi 12 cm, Akrilike	ml	140		
2	An144	Vizim Akrilik	m ²	1,5		
3	An97	F V tabela rrugore STOP	cope	1		
4	An103	F.V. Tabela Rrethore D=60	cope	1		
					Shuma 4	
Total (1-4)						
		Fondi rezerve %	5%			
		Shuma pa TVSH				
		TVSH %	20%			
		Shuma me TVSH				



InfraKonsult
Drejtuesi Ligjor
Ing. Redi STRUGA



BASHKIA SHKODER

MIRATOHET

KRYETAR
VOLTANA ADEMI

PROJEKT-ZBATIM

PREVENTIV I PUNIMEVE

Objekti: "Projektim per objektin: Sistemim asfaltim Rruge te brendshme fshati "Samerisht I Vjeter" (Aksi nr.5)
Faza 1 Km 0+000-Km 0+046

Nr	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
1 - PUNIME PER MBUSHJE DHE GERMIM						
1	3.89/b	Germim dheu	m ³	105		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	105		-
Shuma 1						-
2 - PUNIME PER TRUPIN E RRUGES						
1	An.164/1b	Mbushje me material shkembor	m ³	68		-
2	3.212/d	Shtrese stabilizant t=20 cm	m ²	224		-
3	3.222/1	Shtrese binderi, me granil gure kave , 5 cm, perhapur e ngjeshur me makineri	m ²	221		-
4	3.224/1	Shtrese asfaltobetoni me granil gure kave , 3 cm, perhapur e ngjeshur me makineri e ngjeshur me makineri	m ²	221		-
5	3.212/b	Stabilizant per bankine t=10cm	m ²	30		-
Shuma 2						-
3 - PUNIME NE TROTUAR,BORDURA,KUNETE						
1	An	F V bordura betoni 20x30 cm	ml	58		-
Shuma 3						-
4 - VEPRA ARTI						
1	3.89/b	Germim toke e bute seksion i lire + trans auto	m ³	33		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	33		-
3	3.240	Beton C 12/15 per kemishim tombinoje	m ³	6,8		-
4	3.365	Tombino betoni D=600 mm	ml	7		-
5	An-9	Zhavorr per nivelim	m ³	1,3		-
6	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	15,3		-
7	3.244	Beton C20/25	m ³	7		-
Shuma 4						-
5 - PUNIME SINJALISTIKE						
1	An124	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Akrilike	ml	115		-
2	An144	Vizim Akrilik	m ²	1,5		-
3	An97	F V tabela rrugore STOP	cope	1		-
Shuma 5						-
Total (1-5)						
		Fondi rezerve %	5%			-
		Shuma pa TVSH				-
		TVSH %	20%			-
		Shuma me TVSH				-



InfraKonsult
Drejtuesi Ligjor
Ing. Redi STRUGA