

MIRATOHET
BASHKIA PATOS
KRYETARI
Rajmonda Balilaj

PREVENTIV						
OBJEKTI: RIKONSTRUKSIONI I MAGJISTRALIT KRYESOR DHE RRJETIT TE BRENDSEHEM TE UJESJELLESIT QYTETIT PATOS Loti I (Rrjeti shperndares)						
Nr.	Nr. An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefta
A. LINJAT E UJESJELLESIT RRJETI SHPERNDARES ZONA DUKAS						
1	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	13,983		
2	3.45/1	Germim kanalesh ne toke te zakonshme, me krahe, me seksion deri 0.75 m ²	m ³	1,398		
3	3.2	Prerje bime te vogla Ø-10cm	m ²	40		
4	An	Prerje asfalti me makineri	ml	8,600		
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5km	m ³	9,431		
7	An-49	Prishje struktura prej betoni	m ³	13		
8	2.261	Shtrese rere	m ³	4,142		
9	2.258	Nenshtrese zhavori (per rruget pa asfaltim)	m ³	18		
10	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	5,950		
11	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	11,252		
12	3.212/b	Shtrese stabilizant t=10cm	m ²	11,252		
13	3.222/2	Shtrese binderi me granil gur kave,6cm,me mak.	m ²	3,670		
14	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ²	3,670		
15	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	14		
16	An1	Shtrese rere bituminoze ,10cm,me mak.	m ²	7,582		
17	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm , t = 3.7 mm, PN 10	ml	83		
18	2.491/f	F.V Tuba e rakorderi ujesjellesi PE d=63mm,t = 4.7 mm, PN 10	ml	385		
29	2.491/q	F.V Tuba e rakorderi ujesjellesi PE d=560mm, t=36.8 mm, PN 10	ml	1,062		
30	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm, PN 16	ml	3,143		
31	2.491/f	F.V Tuba e rakorderi ujesjellesi PE d=63mm, PN 16	ml	1,100		
32	An6 T	F.V Tuba e rakorderi ujesjellesi PE d=75mm, PN 16	ml	2,977		
33	2.491/g	F.V Tuba e rakorderi ujesjellesi PE d=90mm, PN 16	ml	2,159		
34	2.491/h	F.V Tuba e rakorderi ujesjellesi PE d=110mm, PN 16	ml	710		
35	2.491/i	F.V Tuba e rakorderi ujesjellesi PE d=125mm, PN 16	ml	527		
36	An7 T	F.V Tuba e rakorderi ujesjellesi PE d=140mm, PN 16	ml	64		
37	An8 T	F.V Tuba e rakorderi ujesjellesi PE d=160mm, PN 16	ml	551		
39	An10 T	F.V Tuba e rakorderi ujesjellesi PE d=200mm, PN 16	ml	151		
43	An14 T	F.V Tuba e rakorderi ujesjellesi PE d=315mm, PN 16	ml	1,981		
44	An15 T	F.V Tuba e rakorderi ujesjellesi PE d=400mm, PN 16	ml	619		
		SHUMA A				
		PUSETAT E SHKARKIMIT DHE AJRIMIT - ANA TEKNOLOGJIKE				
		<i>Ana teknologjike shkarkuesve</i>				
		<i>Ana teknologjike shkarkuesve ne puseten 2-4</i>				
		2/4. Shkarkues Ø 50 mm ne tub Dn75, Dn63, Dn50				
1	An 62/R	F.V. Tee me fllanxhe e Reduktuar DN=50/50 PN16	Cope	1		
2	An 75/R	F.V. Fllanxhe adaptor DN=50 PN16 per tub PE	Cope	2		

PREVENTIV						
OBJEKTI: RIKONSTRUKSIONI I MAGJISTRALIT KRYESOR DHE RRJETIT TE BRENDSEME TE UJESJELLESIT QYTETIT PATOS Loti I (Rrjeti shperndares)						
Nr.	Nr. An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefte
3	An+4.123/1	F.V. Saraçineske gize DN=50 PN16	Cope	1		
4	An 166/R	F.V. Nyje cmontuese DN=50 PN16	Cope	1		
6	An 128/R	F.V. Tub Fllanxe - Fllanxe me fllanxe murale ne mes DN=50 PN16	Cope	1		
		Shuma 2/4				
		TOTALI RADORDERI SHKARKUES	Cope	4		
		2. Ana teknologjike ajrues				
		2/1. Ajrues Ø 50mm ne tub DN160				
1	An 43/R	F.V. Tee me fllanxe e Reduktuar DN= 150/50 PN16	Cope	1		
2	An 86/R	F.V. Fllanxe adaptor DN=150 PN16 per tub PE	Cope	2		
3	An+4.123/1	F.V. Saraçineske gize DN=50 PN16	Cope	1		
4	An	Ajrues DN 50 mm	Cope	1		
5	An 180/R	F.V. Nyje cmontuese DN=150 PN16	Cope	1		
6	An 142/R	F.V. Tub Fllanxe - Fllanxe me fllanxe murale ne mes DN=150 PN16	Cope	2		
		Shuma				
		Shuma (cope)2/1	cope	1		
		2/4 Ajrues Ø 50 mm ne tub Dn75,Dn63,Dn50				
1	An 62/R	F.V. Tee me fllanxe e Reduktuar DN=50/50 PN16	Cope	1		
2	An 75/R	F.V. Fllanxe adaptor DN=50 PN16 per tub PE	Cope	2		
3	An+4.123/1	F.V. Saraçineske gize DN=50 PN16	Cope	1		
4	An 166/R	F.V. Nyje cmontuese DN=50 PN16	Cope	1		
5	An	Ajrues DN 50 mm	Cope	1		
6	An 128/R	F.V. Tub Fllanxe - Fllanxe me fllanxe murale ne mes DN=50 PN16	Cope	1		
		Shuma				
		Shuma (cope)2/4	Cope	4		
		TOTALI RADORDERI AJRUES				
		TOTALI RADORDERI SHKARKUES+AJRUES				
		T. LIDHJET E BANESAVE ME UJE				
T 01		Pusetat vertikale te shperndarjes (ana ndertimore)				
1	3.59/b	Germim themel i vecuar, gropa sip.10-30 m², toke e zak. me h = 1.5 m	m3	1		
2	3.243	Beton C16/20 bazamenti, kollonat & soleta	m3	1.1		
3	2.64/1	Mur me tulle plotë llaç perzier M 15	m3	0.55		
4	2.31	Suva mur tulle llaç perzier M 25	m2	8.1		
5	2.399	Sherbetisje e bojatisje me gelqere	m2	8.1		
6	3.288	Hekur betoni	kg	55		
7	4.3	Konstruksione te thjeshta	kg	61		
8	4.112	Bojatisje nje dore minio e dy duar boje vaji	cope	3.2		
9	An111 / Lidhje	Dryn	cope	1		
		Shuma (1 cope)				
		SHUMA T 01	Cope	120		
T 02		Pusetat vertikale te shperndarjes (ana teknologjike)				
1	3.59/b	Germim themel i vecuar, gropa sip.10-30 m², toke e zak. me h = 1.5 m	m3	6.72		
2	2.36	Mbushje me materialin e dale nga germimi	m3	3.93		
3	2.261	Shtrese rere	m³	1.67		

PREVENTIV						
OBJEKTI: RIKONSTRUKSIONI I MAGJISTRALIT KRYESOR DHE RRJETIT TE BRENDSEHEM TE UJESJELLESIT QYTETIT PATOS Loti I (Rrjeti shperndares)						
Nr.	Nr. An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefte
4	2.258	Nenshtrese zhavori (per rruget pa asfaltim)	m ³	0.308		
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	1.729		
6	3.212/b	Shtrese stabilizant t=10cm	m ²	1.729		
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me mak.	m ²	0.805		
8	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ²	0.805		
9	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	0.462		
10	An1	Shtrese rere bituminoze ,10cm,me mak.	m ²	0.924		
11	2.491/d	Tub HDPE DNDN40 linje - kasete	ml	8		
12	2.491/b	Tub HDPE-DNDN20 per shperndarje ne banesa	ml	200		
13	An112 / Lidhje	Manikote PE 40 mm	cope	1		
14	An113 / Lidhje	Hollandes xingato 1.1/2"	cope	1		
15	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	1		
16	An114 / Lidhje	Kryq xingato 1.1/2" /3/4"	cope	5		
17	An115 / Lidhje	Niple 1.1/2"	cope	5		
18	An116 / Lidhje	Tapa 1.1/2"	cope	1		
19	2.492	Tub xingato 1.1/2"	kg	4		
20	An117 / Lidhje	Niple 3/4"	cope	24		
21	An118 / Lidhje	K/valvol 3/4'	cope	8		
22	2.494/1	Saracineske 3/4"	cope	16		
23	An119 / Lidhje	F.Vendosje Sahat mates uji 3/4	cope	8		
24	An120 / Lidhje	Tapa 3/4"	cope	2		
		Shuma (1 cope)				
		SHUMA T 02	Cope	120		
T 03		Lidhjet e rrjetit me pallatet ekzistues ujesjellesit				
1	An121 / Lidhje	Fasheta PE10DN 40 lidhje nga tubi Ø 75	cope	1		
2	3.87/a	Germim per kanale	m ³	8.4		
3	2.258	Nenshtrese zhavori (per rruget pa asfaltim)	m ³	3.5		
4	2.261	Shtrese rere	m ³	2.1		
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	0.7		
6	3.212/b	Shtrese stabilizant t=10cm	m ²	0.7		
7	3.222/2	Shtrese binderi me granil gur kave,6cm,me mak.	m ²	0.7		
8	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m ²	0.7		
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5km	m ³	8.4		
11	2.491/d	Tub HDPE DN40	ml	10		
12	13/P	Fllanxe adaptor DN 50 mm	cope	1		
13	An 112 / Lidhje	Manikote HDPE-RC DN40	cope	1		
14	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	1		
15	An121 / Lidhje	Hollandez Ø 1 1/2 " = 40 mm	cope	1		
		Shuma (1 cope)				
		SHUMA T 03	Cope	49		
1	An121 / Lidhje	Fasheta PE10DN 40 lidhje nga tubi Ø 75	cope	1		
2	3.87/a	Germim per kanale	m ³	8.4		
3	2.258	Nenshtrese zhavori (per rruget pa asfaltim)	m ³	3.5		

PREVENTIV						
OBJEKTI: RIKONSTRUKSIONI I MAGJISTRALIT KRYESOR DHE RRJETIT TE BRENDSEHEM TE UJESJELLESIT QYTETIT PATOS Loti I (Rrjeti shperndares)						
Nr.	Nr. An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefte
4	2.261	Shtrese rere	m ³	2.1		
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5km	m ³	8.4		
11	2.491/d	Tub HDPE DN40	ml	10		
12	13/P	Fllanxe adaptor DN 50 mm	cope	1		
13	An 112 / Lidhje	Manikote HDPE-RC DN40	cope	1		
14	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	1		
15	An121 / Lidhje	Hollandez Ø 1 1/2 " = 40 mm	cope	1		
		Shuma (1 cope)				
		SHUMA T 04	Cope	27		
1	An121 / Lidhje	Fasheta PE10DN 40 lidhje nga tubi Ø 75	cope	1		
2	3.87/a	Germim per kanale	m ³	8.4		
3	2.258	Nenshtrese zhavori (per rruget pa asfaltim)	m ³	4.9		
4	2.261	Shtrese rere	m ³	2.1		
9	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	0.7		
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5km	m ³	8.4		
11	2.491/d	Tub HDPE DN40	ml	10		
12	13/P	Fllanxe adaptor DN 50 mm	cope	1		
13	An 112 / Lidhje	Manikote HDPE-RC DN40	cope	1		
14	2.494/4	F.V saracineska bronzi Ø 1 1/2 " = 40 mm	cope	1		
15	An121 / Lidhje	Hollandez Ø 1 1/2 " = 40 mm	cope	1		
		Shuma (1 cope)				
		SHUMA T 05	Cope	10		
T 04		Montimi i sahateve ne pallatet ekzistuese ujesjellesit				
1	An123 / Lidhje	Niple 1*2"	cope	3		
2	An124 / Lidhje	K/valvol 1/2'	cope	1		
3	2.494	Saracineske 1/2"	cope	2		
4	An21/Lidhje	F.Vendosje Sahat mates uji 1/2	cope	1		
5	An122 / Lidhje	Kasete metalike 60*40*30 cm	cope	1		
		Shuma (1 cope)	leke			
		SHUMA T 06	cope	560		
T 05		Lidhjet e banesave individuale (me kaseta metalike) ujesjellesit				
1	An14/Lidhje	Fasheta HDPE DN25 lidhje nga tubi Ø 40	cope	1		
2	2.491/b	F.v. Tuba e rakorderi PEØ25mm, PN 10	ml	15		
3	An12/Lidhje	Manikote PE 25	cope	1		
4	An117 / Lidhje	Niple 3/4"	cope	3		
5	An118 / Lidhje	K/valvol 3/4'	cope	1		
6	2 494/1	Saracineske 3/4"	cope	2		
7	An119 / Lidhje	F.Vendosje Sahat mates uji 3/4	cope	1		
8	An122 / Lidhje	Kasete metalike 60*40*30 cm	cope	1		
		Shuma (1 cope)	lek			
		SHUMA T 07	cope	95		
		SHUMA(T 01+T 02+T 03+T 04+T 05+T 06+T 07)				
		TH VEPRAT E ARTIT				
TH 01		KALIMET E TUBACIONEVE NE KANALE				

PREVENTIV						
OBJEKTI: RIKONSTRUKSIONI I MAGJISTRALIT KRYESOR DHE RRJETIT TE BRENDSEHEM TE UJESJELLESIT QYTETIT PATOS Loti I (Rrjeti shperndares)						
Nr.	Nr. An.	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi	Vlefte
1	An 196/R	F.V. Tub DCI , DN50 K 9 , dy anet fllanxhe L=3.7m	Cope	2		
3	An 198/R	F.V. Tub DCI , DN80 K 9 , dy anet fllanxhe L=3.7m	Cope	2		
4	An 199/R	F.V. Tub DCI , DN100 K 9 , dy anet fllanxhe L=3.7m	Cope	2		
		SHUMA TH01 (Leke)				
TH 02		KALIMET E TUBACIONEVE NE TOMBINO				
16	An 209/R	F.V. Tub DCI , DN250 K 9 , dy anet fllanxhe L=1.86m	Cope	2		
20	An 210/R	F.V. Tub DCI , DN50 K 9 , dy anet fllanxhe L=2m	Cope	1		
22	An 212/R	F.V. Tub DCI , DN80 K 9 , dy anet fllanxhe L=2m	Cope	1		
23	An 213/R	F.V. Tub DCI , DN100 K 9 , dy anet fllanxhe L=2m	Cope	1		
27	An 217/R	F.V. Tub DCI , DN250 K 9 , dy anet fllanxhe L=2m	Cope	1		
33	An 219/R	F.V. Bryl 22.5° DCI ,dy ane fllanxhe ,DN50	Cope	4		
35	An 221/R	F.V. Bryl 22.5° DCI ,dy ane fllanxhe ,DN80	Cope	4		
36	An 222/R	F.V. Bryl 22.5° DCI ,dy ane fllanxhe ,DN100	Cope	4		
40	An 226/R	F.V. Bryl 22.5° DCI ,dy ane fllanxhe ,DN250	Cope	4		
46	An 75/R	F.V. Fllanxhe adaptor DN50 PN16 per tub PE	Cope	2		
51	An 72/R	F.V. Fllanxhe adaptor DN80 PN16 per tub PE	Cope	2		
60	An 91/R	F.V. Fllanxhe adaptor DN250 PN16 per tub PE	Cope	2		
62	An 251/R	F.V. Fllanxh adaptor DN100 PN16 per tub celik	Cope	2		
		SHUMA TH02 (Leke)				
		SHUMA TH01+TH02+TH03+TH04 (Leke)				
		U. ANKERAT				
U 01		Ankerat (ana ndertimore)				
1	3.25/a	Germim dheu per bazamentin	m3	2		
2	3.243	Beton C16/20 per bllokun e ankorimit	m3	3		
3	3.765	Hekur betoni	kg	0.04		
4	4.3	Konstruksione te thjeshta per kapjen e tubit	kg	10		
		Shuma (1 cope)				
		SHUMA U 01	Cope	7		
		SHUMA				
		Fondi rezerve	3.5%			
		SHUMA				
		TVSH	20%			
		SHUMA TOTALE				